

## VOLUME 2: EFFECTS ASSESSMENT METHODS AND PHYSICAL SETTING

### TABLE OF CONTENTS

<b>8.0</b>	<b>EFFECTS ASSESSMENT METHODS</b> .....	<b>8-1</b>
8.1	ENVIRONMENTAL ASSESSMENT METHODS .....	8-1
8.1.1	Issues Scoping .....	8-1
8.1.2	Selection of Valued Components .....	8-3
8.1.3	Establishment of Assessment Boundaries .....	8-11
8.1.3.1	Spatial Boundaries .....	8-11
8.1.3.2	Temporal Boundaries .....	8-12
8.1.3.3	Administrative Boundaries .....	8-14
8.1.3.4	Technical Boundaries .....	8-15
8.1.4	Description of Existing Conditions .....	8-15
8.1.4.1	Description of Expected Conditions .....	8-15
8.1.5	Identification of Interactions and Potential Project Effects .....	8-16
8.1.6	Mitigation Measures .....	8-18
8.1.6.1	Adverse Effects .....	8-18
8.1.6.2	Positive Effects .....	8-18
8.1.7	Characterisation of Residual Effects and Context .....	8-18
8.1.8	Determination of Significance of Residual Adverse Effects .....	8-20
8.1.9	Cumulative Effects Assessment .....	8-21
8.1.9.1	Identification of Other Certain and Reasonably Foreseeable Projects and Activities .....	8-22
8.1.9.2	Identification of the Effects of Other Certain and Reasonably Foreseeable Projects and Activities .....	8-27
8.1.9.3	Identification of Cumulative Interactions and Potential Cumulative Effects .....	8-27
8.1.9.4	Mitigation of Cumulative Effects .....	8-29
8.1.9.5	Characterisation of Residual Cumulative Effects and Context .....	8-29
8.1.9.6	Determination of Significance of Residual Adverse Cumulative Effects .....	8-29
8.1.10	Monitoring and Follow-up Programs .....	8-30
8.2	REFERENCES .....	8-31
<b>9.0</b>	<b>PHYSICAL SETTING</b> .....	<b>9-1</b>
9.1	CLIMATE, COASTAL CONDITIONS, AND GEOTECHNICAL CONSIDERATIONS .....	9-1-1
9.1.1	Climate .....	9-1-2
9.1.1.1	Canadian Climate Normals Station Locations .....	9-1-2
9.1.1.2	Precipitation .....	9-1-3
9.1.1.3	Temperature .....	9-1-3

	9.1.1.4	Visibility .....	9.1-8
	9.1.1.5	Humidity .....	9.1-8
	9.1.1.6	Wind Duration, Direction, Speed, and Force .....	9.1-9
9.1.2		Coastal Conditions .....	9.1-11
	9.1.2.1	Groundwater .....	9.1-11
	9.1.2.2	Marine Water Levels .....	9.1-12
	9.1.2.3	Tidal Currents .....	9.1-13
	9.1.2.4	Wave Heights and Storm Surges .....	9.1-14
	9.1.2.5	Sea Level Rise.....	9.1-15
9.1.3		Geotechnical Considerations.....	9.1-16
	9.1.3.1	Site Geology .....	9.1-17
	9.1.3.2	Seismic Activity.....	9.1-18
	9.1.3.3	Submarine Landslides .....	9.1-24
	9.1.3.4	Tsunamis .....	9.1-25
		Subduction Earthquake-generated Tsunamis .....	9.1-25
		Landslide-generated Tsunamis .....	9.1-26
	9.1.3.5	Isostatic Subsidence .....	9.1-27
	9.1.3.6	Delta Foreslope Erosion .....	9.1-29
	9.1.3.7	Geotechnical Stability.....	9.1-29
9.1.4		References .....	9.1-33
9.2		AIR QUALITY .....	9.2-1
	9.2.1	Selection of Air Quality Intermediate Component .....	9.2-1
	9.2.2	Assessment Purpose and Approach .....	9.2-2
		9.2.2.1 Purpose.....	9.2-2
		9.2.2.2 Air Quality Assessment Approach.....	9.2-4
	9.2.3	Summary of Information Sources .....	9.2-4
	9.2.4	Applicable Standards and Criteria for Compounds of Potential Concern ..	9.2-6
		9.2.4.1 Compounds of Potential Concern .....	9.2-6
		9.2.4.2 Air Quality Criteria for Criteria Air Contaminants .....	9.2-7
		9.2.4.3 Air Quality Criteria for Trace Organic Contaminants.....	9.2-10
	9.2.5	Methods.....	9.2-10
		9.2.5.1 Temporal Boundaries .....	9.2-10
		9.2.5.2 Study Area .....	9.2-12
		9.2.5.3 Emissions Inventory Methods.....	9.2-14
		9.2.5.4 Air Dispersion Modelling .....	9.2-19
	9.2.6	Existing Conditions .....	9.2-23
		9.2.6.1 Background Air Quality Concentrations.....	9.2-25
		9.2.6.2 Modelling of Existing Conditions.....	9.2-28
	9.2.7	Expected Conditions .....	9.2-32

	9.2.7.1	Regulatory Initiatives .....	9.2-32
	9.2.7.2	Other Emission Reduction Initiatives .....	9.2-34
	9.2.7.3	Coal Dust from Westshore Terminals.....	9.2-35
	9.2.7.4	Modelling of Expected Conditions 2025.....	9.2-35
9.2.8		Future Conditions with the Project .....	9.2-39
	9.2.8.1	Construction Phase .....	9.2-39
	9.2.8.2	Operation Phase.....	9.2-43
9.2.9		Future Conditions with the Project and Other Projects and Activities ...	9.2-48
	9.2.9.1	Road Traffic for Other Projects and RBT2 .....	9.2-49
	9.2.9.2	Incremental Rail Traffic Associated with RBT2 .....	9.2-49
	9.2.9.3	Marine Vessel Traffic for Other Projects and RBT2 .....	9.2-49
	9.2.9.4	Assessment of Cumulative Change Results .....	9.2-50
9.2.10		Summary of Assessment .....	9.2-59
	9.2.10.1	Predicted Changes in Total Annual Emissions for Greenhouse Gases and Black Carbon from 2010 to 2025 .....	9.2-59
	9.2.10.2	Predicted Changes in Ozone.....	9.2-60
	9.2.10.3	Comparisons of Future Conditions with the Project to Existing Conditions .....	9.2-60
	9.2.10.4	Comparisons of Future Conditions with the Project to Expected Conditions .....	9.2-63
	9.2.10.5	Illustrative Comparisons for Existing, Expected and Future Conditions .....	9.2-66
	9.2.10.6	Assessment of Cumulative Change Summary.....	9.2-67
9.2.11		Uncertainty, Sensitivity, and Reliability .....	9.2-74
9.2.12		References .....	9.2-78
9.3		NOISE AND VIBRATION.....	9.3-1
	9.3.1	Selection of Noise and Vibration Intermediate Component .....	9.3-2
	9.3.2	Assessment Purpose and Approach .....	9.3-2
	9.3.3	Summary of Information Sources .....	9.3-4
	9.3.3.1	Previous Studies of Noise and Vibration at Roberts Bank.....	9.3-4
	9.3.3.2	General Data Used in the Assessment .....	9.3-4
9.3.4		Acoustic Fundamentals and Terminology.....	9.3-6
9.3.5		Applicable Standards and Guidelines .....	9.3-8
9.3.6		Methods.....	9.3-8
	9.3.6.1	Temporal Boundaries .....	9.3-9
	9.3.6.2	Study Area .....	9.3-10
	9.3.6.3	Characterising the Existing Noise and Vibration Environment. ....	9.3-11
	9.3.6.4	Predicting Expected Conditions Noise and Vibration Levels ....	9.3-17
	9.3.6.5	Predicting Future Conditions with the Project.....	9.3-18

9.3.7	Existing Conditions .....	9.3-20
9.3.7.1	Measured Noise and Vibration Levels within the Upland Study Area .....	9.3-20
9.3.7.2	Meteorological Effects .....	9.3-24
9.3.7.3	Modelled Existing Annual Average Noise Levels in the Upland and Marine Study Areas .....	9.3-25
9.3.8	Expected Conditions .....	9.3-29
9.3.8.1	Overview of Expected Conditions .....	9.3-30
9.3.8.2	Annual Average Noise Levels for Expected Conditions.....	9.3-31
9.3.8.3	Expected Conditions - Transient and Impulsive Noise Levels..	9.3-35
9.3.8.4	Expected Conditions - Low-frequency Noise Levels.....	9.3-36
9.3.8.5	Expected Conditions – Vibration Levels.....	9.3-36
9.3.9	Future Conditions with the Project .....	9.3-36
9.3.9.1	Overview of Future Conditions with the Project.....	9.3-36
9.3.9.2	Construction-phase Noise and Vibration.....	9.3-37
9.3.9.3	Operation-phase Noise and Vibration .....	9.3-39
9.3.10	Future Conditions with the Project and Other Certain and Reasonably Foreseeable Projects and Activities.....	9.3-45
9.3.10.1	Potential Cumulative Changes to Noise Environment .....	9.3-49
9.3.10.2	Summary of Incremental Cumulative Change.....	9.3-52
9.3.11	Summary of Assessment .....	9.3-53
9.3.12	Uncertainty, Sensitivity, and Reliability .....	9.3-55
9.3.13	References .....	9.3-58
9.4	LIGHT.....	9.4-1
9.4.1	Selection of Light Intermediate Component .....	9.4-2
9.4.2	Assessment Purpose and Approach .....	9.4-2
9.4.2.1	Aspects Excluded from Assessment of Light .....	9.4-4
9.4.3	Summary of Information Sources .....	9.4-5
9.4.4	Relevant Guidelines .....	9.4-5
9.4.4.1	Light Trespass Classification.....	9.4-6
9.4.4.2	Sky Glow Classification.....	9.4-7
9.4.5	Methods.....	9.4-8
9.4.5.1	Temporal Boundaries .....	9.4-8
9.4.5.2	Study Area .....	9.4-9
9.4.5.3	Study Methods.....	9.4-10
9.4.6	Existing Conditions .....	9.4-12
9.4.7	Expected Conditions .....	9.4-14
9.4.8	Future Conditions with the Project .....	9.4-15
9.4.8.1	Construction .....	9.4-15

	9.4.8.2	Operation .....	9.4-15
9.4.9		Future Conditions with the Project and Other Certain and Reasonably Foreseeable Projects and Activities.....	9.4-19
9.4.10		Summary of Assessment .....	9.4-19
9.4.11		Uncertainty, Sensitivity, and Reliability .....	9.4-19
9.4.12		References .....	9.4-21
9.5		COASTAL GEOMORPHOLOGY .....	9.5-1
9.5.1		Selection of Coastal Geomorphology Intermediate Component .....	9.5-1
9.5.2		Assessment Purpose and Approach .....	9.5-2
	9.5.2.1	Purpose.....	9.5-2
	9.5.2.2	Coastal Geomorphology Assessment Approach.....	9.5-3
9.5.3		Summary of Information Sources .....	9.5-4
9.5.4		Applicable Standards and Criteria .....	9.5-5
9.5.5		Methods.....	9.5-5
	9.5.5.1	Temporal Boundaries .....	9.5-6
	9.5.5.2	Study Area .....	9.5-7
	9.5.5.3	Study Methods.....	9.5-10
9.5.6		Existing Conditions .....	9.5-12
	9.5.6.1	Fraser River.....	9.5-12
	9.5.6.2	Roberts Bank .....	9.5-20
	9.5.6.3	Morphology of Roberts Bank .....	9.5-31
9.5.7		Expected Conditions .....	9.5-41
	9.5.7.1	Construction Phase.....	9.5-41
	9.5.7.2	Operation Phase.....	9.5-41
9.5.8		Future Conditions with the Project .....	9.5-48
	9.5.8.1	Construction Phase.....	9.5-48
	9.5.8.2	Operation Phase.....	9.5-50
9.5.9		Future Conditions with the Project and Other Certain and Reasonably Foreseeable Projects and Activities.....	9.5-64
9.5.10		Summary of Assessment .....	9.5-65
9.5.11		Uncertainty, Sensitivity, and Reliability .....	9.5-68
9.5.12		References .....	9.5-70
9.6		SURFICIAL GEOLOGY AND MARINE SEDIMENT .....	9.6-1
9.6.1		Selection of Intermediate Component.....	9.6-2
9.6.2		Assessment Purpose and Approach .....	9.6-2
9.6.3		Summary of Information Sources .....	9.6-3
9.6.4		Applicable Guidelines and Regulations .....	9.6-5
9.6.5		Methods.....	9.6-5
	9.6.5.1	Temporal Boundaries .....	9.6-5

	9.6.5.2	Study Area .....	9.6-6
	9.6.5.3	Study Methods.....	9.6-7
9.6.6		Existing Conditions .....	9.6-10
	9.6.6.1	Description of Regional and Local Sediment Transport.....	9.6-10
	9.6.6.2	Characteristics of Surficial Sediments in the Fraser River Estuary and Local Study Area .....	9.6-11
	9.6.6.3	Sediment Characteristics in Project-specific Areas .....	9.6-16
9.6.7		Expected Conditions .....	9.6-19
9.6.8		Future Conditions with the Project .....	9.6-19
	9.6.8.1	Construction .....	9.6-20
	9.6.8.2	Operation .....	9.6-23
9.6.9		Future Conditions with the Project and Other Certain and Reasonably Foreseeable Projects and Activities.....	9.6-25
9.6.10		Summary of Assessment .....	9.6-25
9.6.11		Uncertainty, Sensitivity, and Reliability .....	9.6-26
9.6.12		References .....	9.6-28
9.7		MARINE WATER QUALITY .....	9.7-1
	9.7.1	Selection of Intermediate Component.....	9.7-1
	9.7.2	Assessment Purpose and Approach .....	9.7-2
	9.7.3	Summary of Information Sources .....	9.7-3
	9.7.4	Applicable Guidelines .....	9.7-4
	9.7.5	Methods.....	9.7-5
	9.7.5.1	Temporal Boundaries .....	9.7-5
	9.7.5.2	Study Area .....	9.7-6
	9.7.5.3	Study Methods.....	9.7-6
9.7.6		Existing Conditions .....	9.7-8
	9.7.6.1	Temperature.....	9.7-8
	9.7.6.2	Salinity .....	9.7-9
	9.7.6.3	Dissolved Oxygen and pH.....	9.7-13
	9.7.6.4	Total Suspended Solids and Turbidity .....	9.7-13
	9.7.6.5	Nutrients.....	9.7-14
	9.7.6.6	Contaminants of Potential Concern .....	9.7-15
9.7.7		Expected Conditions .....	9.7-16
9.7.8		Future Conditions with the Project .....	9.7-17
	9.7.8.1	Construction Phase.....	9.7-17
	9.7.8.2	Operation .....	9.7-24
9.7.9		Future Conditions with the Project and Other Certain and Reasonably Foreseeable Projects and Activities.....	9.7-27
9.7.10		Summary of Assessment .....	9.7-28

9.7.11	Uncertainty, Sensitivity, and Reliability .....	9.7-29
9.7.12	References .....	9.7-31
9.8	UNDERWATER NOISE .....	9.8-1
9.8.1	Selection of Underwater Noise Intermediate Component .....	9.8-1
9.8.2	Assessment Purpose and Approach .....	9.8-2
9.8.3	Summary of Information Sources .....	9.8-3
	9.8.3.1 Acoustic Fundamentals and Terminology .....	9.8-4
9.8.4	Underwater Noise Effects Guidelines.....	9.8-5
9.8.5	Methods.....	9.8-6
	9.8.5.1 Temporal Boundaries .....	9.8-7
	9.8.5.2 Study Areas.....	9.8-7
	9.8.5.3 Technical Boundaries .....	9.8-8
	9.8.5.4 Methods to Characterise the Existing Underwater Acoustic Environment.....	9.8-8
	9.8.5.5 Methods for Predicting Future Conditions of Underwater Noise with the Project.....	9.8-11
	9.8.5.6 Methods for Predicting Future Conditions with and without the Project and Other Certain and Reasonably Foreseeable Projects and Activities .....	9.8-14
9.8.6	Existing Conditions .....	9.8-15
	9.8.6.1 Hydrophone Measured Underwater Noise Levels in the Local Study Area .....	9.8-15
	9.8.6.2 Hydrophone Measured Existing Underwater Noise Levels in the Regional Study Area .....	9.8-16
	9.8.6.3 Modelled Existing Underwater Noise Levels in the Local Study Area and Regional Study Area .....	9.8-16
9.8.7	Future Conditions with the Project .....	9.8-16
	9.8.7.1 Underwater Noise during Construction Phase .....	9.8-16
	9.8.7.2 Operation-phase Underwater Noise.....	9.8-18
9.8.8	Future Conditions with and without the Project and Other Certain and Reasonably Foreseeable Projects and Activities .....	9.8-21
	9.8.8.1 Modelled Underwater Noise Levels in the Regional Study Area.....	9.8-22
9.8.9	Summary of Assessment .....	9.8-24
9.8.10	Uncertainty, Sensitivity, and Reliability .....	9.8-25
	9.8.10.1 Noise Propagation Modelling and Mapping.....	9.8-25
9.8.11	References .....	9.8-28

**List of Tables**

Table 8-1	Intermediate Component and Valued Component Linkages .....	8-9
Table 8-2	Selected Valued Components and Sub-components .....	8-10
Table 8-3	Spatial Boundary Definitions.....	8-12
Table 8-4	Template for Identification of Potential Project Interactions with a Valued Component for Construction or Operation Phase.....	8-17
Table 8-5	Criteria Used to Characterise Residual Effects .....	8-19
Table 8-6	Template for Residual Effect Summary.....	8-19
Table 8-7	Template for Summaries of Valued Component Significance Determination of Residual Effects .....	8-21
Table 8-8	Project and Activity Inclusion List.....	8-24
Table 8-9	Template for Valued Component-specific Potential Cumulative Interactions and Effects .....	8-28
Table 9.1.1-1	Canadian Climate Normals Stations Located Near the Project .....	9.1-3
Table 9.1.1-2	Climate Normals (Temperature and Precipitation) for Delta Tsawwassen Beach Station (1981 to 2010).....	9.1-6
Table 9.1.1-3	Climate Normals (Temperature and Precipitation) for Vancouver International Airport Station (1981 to 2010) .....	9.1-7
Table 9.1.1-4	Monthly Average Visibility at the Vancouver International Airport Station (1981 to 2010) .....	9.1-8
Table 9.1.1-5	Wind Station Locations Near the Project.....	9.1-9
Table 9.1.1-6	Primary and Secondary Directions for Storm Threshold Winds .....	9.1-10
Table 9.1.2-1	Water Level Stations .....	9.1-12
Table 9.1.2-2	Tidal Levels at the Project Area, based on Tsawwassen Station.....	9.1-13
Table 9.1.2-3	Extreme Water Levels at the Project Area.....	9.1-13
Table 9.1.2-4	Measured Maximum Tidal Currents Near the Project Area .....	9.1-14
Table 9.1.2-5	Extreme Wave Heights Modelled for the Project Area .....	9.1-15
Table 9.1.3-1	Shaking Levels at Roberts Bank Terminal 2 from Regional Earthquake Sources and the Cascadia Subduction Zone.....	9.1-23
Table 9.1.3-2	Estimates of Isostatic Subsidence or Rise of the Seaward Edge of the Fraser River Delta, Including the Vicinity of the Project Site.....	9.1-28
Table 9.1.3-3	Summary of Estimated Settlements in the Project Area Following Preloading .	9.1-29
Table 9.1.3-4	Summary of Geotechnical Stability Assessments .....	9.1-31
Table 9.2-1	Air Quality Studies to Support the Assessment.....	9.2-3
Table 9.2-2	Historical Roberts Bank Studies .....	9.2-5
Table 9.2-3	Information by Subject Area.....	9.2-6
Table 9.2-4	Air Quality Criteria for Criteria Air Contaminants.....	9.2-9
Table 9.2-5	Air Quality Criteria for Trace Organic Contaminants .....	9.2-10
Table 9.2-6	Air Quality Study Scenarios .....	9.2-15
Table 9.2-7	Projected Cargo Volumes for Existing and Future Conditions .....	9.2-16



Table 9.2-8	Annual Activity Levels .....	9.2-17
Table 9.2-9	Lower Fraser Valley Air Quality Trends 1990 to 2030 (MV 2013) .....	9.2-23
Table 9.2-10	Background Concentrations for Criteria Air Contaminants .....	9.2-27
Table 9.2-11	Background Concentrations for Trace Organic Contaminants .....	9.2-27
Table 9.2-12	Existing Conditions - Annual Emissions for Greenhouse Gas and Black Carbon	9.2-28
Table 9.2-13	Existing Conditions - Predicted Maximum Concentrations for Gaseous Criteria Air Contaminants and Formaldehyde .....	9.2-30
Table 9.2-14	Existing Conditions - Predicted Maximum Concentrations for Particulate Criteria Air Contaminants.....	9.2-31
Table 9.2-15	Estimated Maximum Reductions of Ship at Berth Emissions at Deltaport Terminal due to Shore Power – Gaseous and Particulate CACs.....	9.2-35
Table 9.2-16	Estimated Maximum Reductions of Ship at Berth Emissions at Deltaport Terminal due to Shore Power – GHG and Black Carbon.....	9.2-35
Table 9.2-17	Expected Conditions - Annual Greenhouse Gas and Black Carbon Emissions ..	9.2-36
Table 9.2-18	Expected Conditions - Predicted Maximum Concentrations for Gaseous Criteria Air Contaminants and Formaldehyde .....	9.2-37
Table 9.2-19	Expected Conditions - Predicted Maximum Concentrations for Particulate Criteria Air Contaminants.....	9.2-38
Table 9.2-20	Predicted Maximum Concentrations for Gaseous Criteria Air Contaminants and Formaldehyde ( $\mu\text{g}/\text{m}^3$ ) – Average Day Project Construction (Project Only) ....	9.2-40
Table 9.2-21	Predicted Maximum Concentrations for Gaseous CACs and Formaldehyde - Average Day Project Construction plus Expected Conditions (Operations at Westshore Terminals, Deltaport Terminal and B.C. Ferries Terminal) .....	9.2-41
Table 9.2-22	Predicted Maximum Particulate Criteria Air Contaminant Concentrations for Average Day Project Construction Activities (Project Only) .....	9.2-42
Table 9.2-23	Predicted Maximum Particulate CAC Concentrations for Average Day Project Construction Activities plus Expected Conditions (Operations at Westshore Terminals, Deltaport Terminal and the B.C. Ferries Terminal).....	9.2-43
Table 9.2-24	Future Conditions with the Project - Annual Greenhouse Gas and Black Carbon Emissions .....	9.2-44
Table 9.2-25	Future Conditions - Predicted Maximum Concentrations for Gaseous Criteria Air Contaminants and Formaldehyde .....	9.2-45
Table 9.2-26	Future Conditions - Predicted Maximum Particulate Criteria Air Contaminant Concentrations .....	9.2-46
Table 9.2-27	Predicted Concentrations for Ozone .....	9.2-47
Table 9.2-28	Estimated Maximum Reductions of Ship at Berth Emissions at RBT2 due to Shore Power – Gaseous and Particulate Criteria Air Contaminants.....	9.2-48
Table 9.2-29	Estimated Maximum Reductions of Ship at Berth Emissions at RBT2 due to Shore Power – GHG and Black Carbon .....	9.2-48
Table 9.2-30	Future Conditions with the Project and Other Certain and Reasonably Foreseeable Projects and Activities - Predicted CO Concentrations .....	9.2-51

Table 9.2-31	Future Conditions with the Project and Other Certain and Reasonably Foreseeable Projects and Activities - Predicted NO <sub>2</sub> Concentrations.....	9.2-52
Table 9.2-32	Future Conditions with the Project and Other Certain and Reasonably Foreseeable Projects and Activities - Predicted SO <sub>2</sub> Concentrations.....	9.2-53
Table 9.2-33	Future Conditions with the Project and Other Certain and Reasonably Foreseeable Projects and Activities - Predicted Formaldehyde Concentrations .....	9.2-55
Table 9.2-34	Future Conditions with the Project and Other Certain and Reasonably Foreseeable Projects and Activities - Predicted PM Concentrations .....	9.2-56
Table 9.2-35	Future Conditions with the Project and Other Certain and Reasonably Foreseeable Projects and Activities - Predicted PM <sub>10</sub> Concentrations.....	9.2-57
Table 9.2-36	Future Conditions with the Project and Other Certain and Reasonably Foreseeable Projects and Activities - Predicted PM <sub>2.5</sub> Concentrations .....	9.2-58
Table 9.2-37	A Comparison of Predicted Changes in Total Annual Emissions for Greenhouse Gas and Black Carbon .....	9.2-59
Table 9.2-38	Anticipated Percent Change in Maximum Predicted CO, NO <sub>2</sub> , SO <sub>2</sub> and Formaldehyde Concentrations in Future Conditions with the Project Compared to Existing Conditions .....	9.2-62
Table 9.2-39	Future Conditions with the Project Compared to Existing Conditions as Percent Change in Maximum Predicted PM Concentrations .....	9.2-63
Table 9.2-40	Future Conditions with the Project Compared to Expected Conditions as Percent Change in Maximum Predicted CO, NO <sub>2</sub> , SO <sub>2</sub> and Formaldehyde Concentrations .....	9.2-65
Table 9.2-41	Future Conditions with the Project Compared to Expected Conditions as Percent Change in Maximum Predicted PM Concentrations .....	9.2-65
Table 9.2-42	Estimated Percent Cumulative Change from Expected Conditions - Predicted CO Concentrations .....	9.2-68
Table 9.2-43	Estimated Percent Cumulative Change from Expected Conditions - Predicted NO <sub>2</sub> Concentrations .....	9.2-69
Table 9.2-44	Estimated Percent Cumulative Change from Expected Conditions - Predicted SO <sub>2</sub> Concentrations .....	9.2-70
Table 9.2-45	Estimated Percent Cumulative Change from Expected Conditions - Predicted Formaldehyde Concentrations.....	9.2-71
Table 9.2-46	Estimated Percent Cumulative Change from Expected Conditions - Predicted PM Concentrations .....	9.2-72
Table 9.2-47	Estimated Percent Cumulative Change from Expected Conditions - Predicted PM <sub>10</sub> Concentrations .....	9.2-73
Table 9.2-48	Estimated Percent Cumulative Change from Expected Conditions - Predicted PM <sub>2.5</sub> Concentrations .....	9.2-74
Table 9.2-49	Measures to Address Uncertainty - Activity Levels .....	9.2-76
Table 9.2-50	Measures to Address Uncertainty and Model Validation – CALPUFF and CALMET .....	9.2-77
Table 9.2-51	Measures to Address Uncertainty and Model Validation – MODEL RESULTS....	9.2-77

Table 9.3-1	Noise and Vibration Studies to Support the Assessment .....	9.3-3
Table 9.3-2	Information by Subject Area.....	9.3-5
Table 9.3-3	Sound Pressure Level of Common Sounds .....	9.3-6
Table 9.3-4	Perceptibility of Noise Level Increases.....	9.3-7
Table 9.3-5	Standards and Guidelines Used for Noise and Vibration Assessment .....	9.3-8
Table 9.3-6	Summary of Sites and Measurement Details for the Characterisation of the Existing Noise and Vibration Environment .....	9.3-14
Table 9.3-7	Daily Average Noise Levels at Sites 3, 4, and 5 .....	9.3-20
Table 9.3-8	Impulsive Noise Events and Levels .....	9.3-22
Table 9.3-9	Noise Event Maximum Levels and Sound Exposure Levels from Transient Rail Noise Events at Site 3.....	9.3-22
Table 9.3-10	Comparison of A- and C-weighted Existing Nighttime Noise Levels .....	9.3-23
Table 9.3-11	Existing Ground-borne Vibration Measurement Results .....	9.3-24
Table 9.3-12	Meteorological Conditions during July 2013 Noise Measurements .....	9.3-25
Table 9.3-13	Modelled Annual Average Existing Noise Levels .....	9.3-26
Table 9.3-14	Future Projects Included in Expected Conditions Model.....	9.3-29
Table 9.3-15	Expected Annual Average Noise Levels in 2025 .....	9.3-31
Table 9.3-16	Estimated Annual Average Noise Levels throughout the Upland Study Area for Expected Conditions.....	9.3-31
Table 9.3-17	Expected Conditions - Predicted Numbers of Future Impulsive and Transient Noise Events .....	9.3-35
Table 9.3-18	Predicted Daytime, Nighttime, and Day-night Average Noise Levels and Noise Level Increases during Project Construction.....	9.3-38
Table 9.3-19	Predicted Daytime Noise Levels in Marine Areas during Project Construction..	9.3-39
Table 9.3-20	Predicted Future Daytime, Nighttime, and Day-night Annual Average Noise Levels with Project Operation.....	9.3-40
Table 9.3-21	Estimated Annual Average Future Noise Levels throughout the Upland Study Area with Project Operation.....	9.3-41
Table 9.3-22	Potential Changes to Noise and Vibration from Other Certain and Reasonably Foreseeable Projects and Activities .....	9.3-46
Table 9.3-23	Forecast Increases in Volumes on Deltaport Way and the Roberts Bank Rail Corridor .....	9.3-49
Table 9.3-24	Incremental Cumulative Changes due to Volume Increases on Deltaport Way and the Roberts Bank Rail Corridor.....	9.3-50
Table 9.3-25	Summary of Changes to Noise Environments within the Local Study Area .....	9.3-55
Table 9.4-1	Light Studies to Support the Assessment .....	9.4-4
Table 9.4-2	Illumination Levels Associated with Common Sources .....	9.4-6
Table 9.4-3	Environmental Light Classification .....	9.4-7
Table 9.4-4	Sky Glow in Percent above Natural Dark Sky Background .....	9.4-7
Table 9.4-5	Zone Classifications for Sky Glow .....	9.4-8

Table 9.4-6	Points of Reception .....	9.4-10
Table 9.4-7	Description of Observed Light Conditions.....	9.4-12
Table 9.4-8	Existing Illuminance Levels and Average Sky Quality Levels and Classifications.....	9.4-13
Table 9.4-9	Predicted Project-related Changes in Light Trespass Levels .....	9.4-16
Table 9.4-10	Predicted Changes in Sky Glow .....	9.4-16
Table 9.5-1	Coastal Geomorphology Studies.....	9.5-3
Table 9.5-2	Summary of the Assessment of Physical Parameters over Time .....	9.5-7
Table 9.5-3	Description of Biosedimentological Zones on Roberts Bank.....	9.5-23
Table 9.5-4	Wave Conditions at Roberts Bank for an Exceedance Frequency of 12 Hours per Year .....	9.5-29
Table 9.5-5	Water Levels in the Strait of Georgia near Tsawwassen (Station 7590) .....	9.5-29
Table 9.5-6	Predicted Morphological Changes from the Project Footprint.....	9.5-65
Table 9.6-1	Studies to Support the Surficial Geology and Marine Sediment Assessment .....	9.6-3
Table 9.6-2	Summary of Modelling Scenarios for Roberts Bank Terminal 2 Construction Activities .....	9.6-9
Table 9.6-3	Summary of Previous Studies in Areas Near and Relevant to Project Activities.....	9.6-16
Table 9.6-4	Range of Contaminant Levels in Sediment for Project Activity Areas Compared to Reference Criteria.....	9.6-17
Table 9.6-5	Summary of Predicted Sediment Deposition Results Model Scenario for Roberts Bank Terminal 2 Construction Activities .....	9.6-21
Table 9.7-1	Marine Water Quality Studies to Support the Assessment .....	9.7-3
Table 9.7-2	Canadian Water Quality Guidelines for the Protection of Aquatic Life - Total Suspended Solids .....	9.7-4
Table 9.7-3	Summary of Total Suspended Solids and Turbidity Results for Roberts Bank (2004 to 2014).....	9.7-13
Table 9.7-4	Model Predictions for Total Suspended Solids Concentrations Increasing by Greater than 5mg/L from Assumed 0 mg/L Background for Dredging and Disposal Activities .....	9.7-20
Table 9.8-1	Underwater Noise Studies to Support the Assessment.....	9.8-3
Table 9.8-2	Underwater Noise Modelling Studies Contributing to Project-related Predictions.....	9.8-3
Table 9.8-3	Project Construction Activities Modelled for Underwater Noise Levels.....	9.8-12
Table 9.8-4	Radii (R95%) of Sound Pressure Level Contours for Continuous Construction Scenarios .....	9.8-17
Table 9.8-5	Radii (R95%) of Sound Pressure Level Contours for Vibratory Piling Construction Scenarios .....	9.8-18
Table 9.8-6	Radii (R95%) of Sound Pressure Level Contours for Operation Scenarios .....	9.8-19
Table 9.8-7	Comparison of Underwater Noise Levels at Four Locations in the Regional Effects Assessment Study Area in January and July for Existing, Future Conditions without the Project, and Future Conditions with the Project.....	9.8-23

**List of Figures (*within text*)**

Figure 8-1	Valued Component Selection Process.....	8-4
Figure 8-2	Example of Pathway of Effects .....	8-7
Figure 9.1.1-3	Average Monthly Precipitation and Temperature at Delta Tsawwassen Beach Station (1981 to 2010).....	9.1-4
Figure 9.1.1-4	Average Monthly Precipitation and Temperature at Vancouver International Airport Station (1981 to 2010).....	9.1-5
Figure 9.1.3-1	Plate Tectonic Set-up and Locations of Some of the Past Major Earthquakes..	9.1-19
Figure 9.1.3-2	Earthquake Epicentres with Magnitude Greater than or Equal to 2 within 100 Kilometres of the Project .....	9.1-20
Figure 9.1.3-3	Earthquake Epicentres with Magnitude Greater than 5 within 100 Kilometres of the Project .....	9.1-21
Figure 9.2-1	Local Study Area and Modelling Area .....	9.2-13
Figure 9.2-2	CALPUFF Model Receptor Grid Spacing within Local Study Area.....	9.2-21
Figure 9.2-3	Discrete Receptor Locations within Local Study Area .....	9.2-22
Figure 9.2-4	Annual Emissions of CO and NO <sub>x</sub> in Future Conditions with the Project Compared to Existing Conditions .....	9.2-61
Figure 9.2-5	Annual Emissions of SO <sub>2</sub> , Formaldehyde and PM <sub>2.5</sub> in Future Conditions with the Project Compared to Existing Conditions .....	9.2-61
Figure 9.2-6	Annual Emissions of CO and NO <sub>x</sub> in Future Conditions with the Project Compared to Expected Conditions.....	9.2-64
Figure 9.2-7	Annual Emissions of SO <sub>2</sub> , Formaldehyde and PM <sub>2.5</sub> in Future Conditions with the Project Compared to Expected Conditions.....	9.2-64
Figure 9.3-6	July 22 to 24, 2013 and Long-term Wind Roses as Recorded at Sand Heads Weather Station .....	9.3-16
Figure 9.3-7	Existing (2013) Day-night Average Level Contours in Upland Study Area .....	9.3-27
Figure 9.3-8	Existing (2013) Daytime Equivalent Level Contours in Marine Study Area.....	9.3-28
Figure 9.3-9	Expected Conditions – Day-night Average Contours in Upland Study Area .....	9.3-33
Figure 9.3-10	Expected Conditions – Daytime Noise Contours in Marine Areas.....	9.3-34
Figure 9.3-11	Project Operation – Day-night Annual Average Sound Level Contours in Upland Study Area .....	9.3-42
Figure 9.3-12	Project Operation – Daytime Equivalent Sound-Level Contours in Marine Areas.....	9.3-43
Figure 9.4-2	Photo of the Existing Sky at Point of Reception 2 .....	9.4-18
Figure 9.4-3	Photo of the Predicted Sky at Point of Reception 2 .....	9.4-18
Figure 9.5-1	Coastal Geomorphology Local Study Area.....	9.5-8
Figure 9.5-2	Spatial Extent of Coastal Geomorphology Numerical Modelling .....	9.5-9
Figure 9.5-3	TELEMAC Model Coupling Flow Diagram .....	9.5-11
Figure 9.5-4	Fraser River Watershed Boundaries and Sub-boundaries .....	9.5-13
Figure 9.5-5	Growth of the Fraser Delta and Floodplain over the Last 10,000 Years.....	9.5-14
Figure 9.5-6	Lower Fraser River Floodplain (Flood Risk Areas).....	9.5-15

Figure 9.5-7 Annual Hydrographs of Fraser River at Hope ..... 9.5-16

Figure 9.5-8 Distributary Channels of the Lower Fraser River ..... 9.5-17

Figure 9.5-9 Portion of 1999 Landsat Image of the Strait of Georgia Showing Distribution of the Fraser River Plume during a Summer Ebbing Tide..... 9.5-19

Figure 9.5-10 Vertical Velocity Map of the Western Part of Metro Vancouver ..... 9.5-20

Figure 9.5-11 Biosedimentological Zonation on Roberts Bank Overlain on Multi-beam Image Showing the Subtidal Portion of the Delta..... 9.5-22

Figure 9.5-12 Fraser River Delta Marsh Development between 1930 and 2004 ..... 9.5-24

Figure 9.5-13 Bathymetry of Southern Roberts Bank ..... 9.5-26

Figure 9.5-14 Hypsometry of Roberts Bank on the North Side of the Causeway ..... 9.5-27

Figure 9.5-15 Wind Rose for Roberts Bank Based on Wind Data Measured at Sand Heads from 1991 to 2013 ..... 9.5-28

Figure 9.5-16 Tidal Amplitude Calculated Based on the Tsawwassen Gauge for 2012..... 9.5-30

Figure 9.5-17 Observed Changes in Alignment of Canoe Passage Outlet Channel across Roberts Bank over the Past 74 years..... 9.5-32

Figure 9.5-18 Topographic Changes on the Tidal Flats from 1967 to 2011..... 9.5-33

Figure 9.5-19 Topographic Changes on the Tidal Flats from 2002 to 2011..... 9.5-34

Figure 9.5-20 Overview of the Ridge and Runnel Complex..... 9.5-36

Figure 9.5-21 Overview of Biomat in the Inter-causeway Area ..... 9.5-37

Figure 9.5-22 Salt Marsh Plants Occupying the Higher Elevations of the Ridge and Runnel Complex North of the Roberts Bank Causeway ..... 9.5-38

Figure 9.5-23 Profiles across Roberts Bank Based on 2011 LiDAR Data and Bathymetry Survey ....  
..... 9.5-39

Figure 9.5-24 Projected Sea Level Rise Used in Ministry of Environment Climate Change Adaptation Guidelines..... 9.5-42

Figure 9.5-25 Predicted Effects of Sea Level Rise on Fiftieth Percentile Wave Heights (Expected Conditions Compared to Existing Conditions) – Winter Season (October to December) ..... 9.5-44

Figure 9.5-26 Morphodynamic Evolution of the Tidal Flats in the Local Study Area based on Numerical Modelling after 1,440 Simulated Days under Expected Conditions Case...  
..... 9.5-47

Figure 9.5-27 Extents of Temporary Drainage Channel Formation during the Construction Phase Associated with the Causeway ..... 9.5-50

Figure 9.5-28 Predicted Change in Fiftieth Percentile Currents Associated with the Project Footprint (Future Conditions with the Project Compared to Existing Conditions) – Freshet Period (May to July)..... 9.5-52

Figure 9.5-29 Predicted Change in Fiftieth Percentile Currents Associated with the Project Footprint (Future Conditions with the Project Compared to Existing Conditions) – Non-freshet Period (October to December) ..... 9.5-53

Figure 9.5-30 Predicted Change in Fiftieth Percentile Wave Height Associated with the Project Footprint (Future Conditions with the Project Compared to Existing Conditions) – Summer Season (May to July) ..... 9.5-55

Figure 9.5-31	Predicted Change in Fiftieth Percentile Wave Height Associated with the Project Footprint (Future Conditions with the Project Compared to Existing Conditions) – Winter Season (October to December).....	9.5-56
Figure 9.5-32	Morphodynamic Evolution from Tidal Currents after 1,440 Simulated Days – Future Conditions with Project Case .....	9.5-59
Figure 9.5-33	Morphodynamic Evolution from Tidal Currents after 1,440 Simulated Days – Difference between Expected Conditions and Future Conditions With Project Cases . .....	9.5-61
Figure 9.5-34	Schematic Layout of Project’s Expanded Tug Basin and Existing Tug Basin Features .....	9.5-63
Figure 9.5-35	Approximate Spatial Extent of Potential Changes Associated with the Project Footprint .....	9.5-66
Figure 9.6-5	Copper Concentration in Roberts Bank Surface Sediment as a Function of Clay Content.....	9.6-13
Figure 9.7-3	Existing Conditions 50 <sup>th</sup> -percentile Salinity Map for the 2012 Freshet Period (May to July) .....	9.7-11
Figure 9.7-4	Existing Conditions 50 <sup>th</sup> -percentile Salinity Map for the 2012 Non-Freshet Period (October to December).....	9.7-11
Figure 9.7-6	Hourly Variation in Salinity and Tide Height at Station T5 for the Period June 11 to June 24, 2012 Based on TELEMAC Model Results.....	9.7-12
Figure 9.7-7	Hourly Variation in Salinity and Tide Height at Station T6 for the Period June 11 to June 24, 2012 Based on TELEMAC Model Results.....	9.7-12
Figure 9.7-12	Predicted Change in 50 <sup>th</sup> -percentile Salinity Associated with the Proposed Terminal Footprint – Freshet Period (May to July).....	9.7-25
Figure 9.7-13	Predicted Change in 50 <sup>th</sup> -percentile Salinity Associated with the Proposed Terminal Footprint – Non-freshet Period (October to December) .....	9.7-26
Figure 9.8-2	Modelling Locations of Modelled Underwater Noise Levels from Commercial Vessel Traffic in the Local Study Area and Regional Study Area .....	9.8-11
Figure 9.8-4	Modelled Increase in Underwater Noise Above Mean Existing Conditions from a Container Ship Call at Roberts Bank Terminal 2 including Approach, Berthing, Unberthing, and Departure.....	9.8-21

**List of Figures (*Large-format figures in Volume 2 Figures*)**

Figure 8-3	Other Certain and Reasonably Foreseeable Projects
Figure 9.1.1-1	Canadian Climate Normals Stations Located Near the Project
Figure 9.1.1-2	Wind Speed and Direction at Four Wind Stations in Proximity to the Project
Figure 9.1.3-4	Sediment Deposition Model
Figure 9.2-8	2010 Existing Conditions Comparison of Maximum Hourly NO <sub>2</sub> Concentration
Figure 9.2-9	Comparison of Concentration Isoleths Generated With and Without Background
Figure 9.2-10	Maximum 1-hour NO <sub>2</sub> Concentrations (µg/m <sup>3</sup> ) with 98 <sup>th</sup> Percentile Background
Figure 9.2-11	Maximum 1-hour SO <sub>2</sub> Concentrations (µg/m <sup>3</sup> ) with 98 <sup>th</sup> Percentile Background
Figure 9.2-12	Maximum 24-hour PM <sub>2.5</sub> Concentrations (µg/m <sup>3</sup> ) with 98 <sup>th</sup> Percentile Background

Figure 9.3-1	Upland Noise and Vibration Study Area
Figure 9.3-2	Marine Above-Water Noise and Vibration Study Area
Figure 9.3-3	Noise and Vibration Study Area for Assessment of Cumulative Change
Figure 9.3-4	Upland Noise and Vibration Existing Noise Measurement Sites
Figure 9.3-5	Upland Noise and Vibration Sub-Areas
Figure 9.4-1	Light Points of Reception
Figure 9.6-1	Surficial Geology and Marine Sediment Study Area
Figure 9.6-2	Sediment Sampling Locations for Sediment and Water Quality Characterisation Studies
Figure 9.6-3	Sediment Sampling Locations for Sediment Characteristics in the Context of Construction-related Sediment Re-suspension and Marine Discharge
Figure 9.6-4	Percent Clay Content Distribution for 2012-2013 Samples
Figure 9.6-6	Surficial Sediment Chloride Concentrations Distribution for 2012-2013 Samples
Figure 9.6-7	Percent Coal Distribution in 2012-2013 Surficial Sediments Samples
Figure 9.6-8	Total Sediment Deposition Thickness Prediction for Dredge Basin and ITP Activities
Figure 9.6-9	Total Sediment Deposition Grain Size (D50) Prediction for Dredge Basin and ITP Activities
Figure 9.6-10	Total Sediment Deposition Accumulation Thickness Prediction for DAS Discharges of Water Containing Dredge Basin Dredgeate and VEF Materials
Figure 9.6-11	Total Sediment Deposition Grain Size (D50) Prediction for DAS Discharges of Water Containing Dredge Basin Dredgeate and VEF Materials
Figure 9.6-12	Total Sediment Deposition Thickness Prediction for DAS Discharge of Water Containing ITP Stored Sands
Figure 9.6-13	Total Sediment Deposition Grain Size (D50) Prediction for DAS Discharge of Water Containing ITP Stored Sands
Figure 9.6-14	Total Sediment Deposition Thickness Prediction for Tug Basin Dredging and Dredgeate Surface Disposal
Figure 9.6-15	Total Sediment Deposition Grain Size (D50) Prediction for Tug Basin Dredging and Dredgeate Surface Disposal
Figure 9.7-1	Marine Water Quality Study Area
Figure 9.7-2	Marine Water Quality Sampling Locations within the LSA
Figure 9.7-5	Locations Where Hourly Salinity was Extracted from the TELEMAC Model
Figure 9.7-8	Prediction for TSS Levels Exceeding 5 mg/L during Dredging of Dredge Basin and ITP Activities
Figure 9.7-9	Prediction for TSS Levels Exceeding 5 mg/L for Discharge of Sediment-laden Water Containing Dredge Basin Dredgeate and VEF Materials
Figure 9.7-10	Prediction for TSS Levels Exceeding 5 mg/L for Discharge of Sediment-laden Water Containing ITP Stored Sands
Figure 9.7-11	Prediction for TSS Levels Exceeding 5 mg/L for Tug Basin Activities
Figure 9.8-1	Study Areas for Underwater Noise
Figure 9.8-3	Mean Predicted Existing and Future Underwater Sound Pressure Levels for January and July



## List of Appendices

Appendix 8-A	Valued Component Selection Rationale
Appendix 8-B	Project Interaction Matrix
Appendix 9.2-A	Roberts Bank Terminal 2 Technical Report Air Quality Study
Appendix 9.2-B	Rationale for Inclusion/Exclusion of Other Certain and Reasonably Foreseeable Projects and Activities in the Cumulative Change Assessment of Air Quality
Appendix 9.3-A	Noise and Vibration Technical Report
Appendix 9.3-B	Rationale for Inclusion / Exclusion of Other Certain and Reasonably Foreseeable Projects and Activities in the Noise and Vibration Assessment of Cumulative Change
Appendix 9.4-A	Roberts Bank Terminal 2 Light Assessment Study
Appendix 9.4-B	Rationale for Exclusion of Other Certain and Reasonably Foreseeable Projects and Activities in the Light Assessment of Cumulative Change
Appendix 9.5-A	Roberts Bank Terminal 2 Technical Report, Coastal Geomorphology Study
Appendix 9.5-B	Rationale for Exclusion of Other Certain and Reasonably Foreseeable Projects in the Cumulative Change Assessment of Coastal Geomorphology
Appendix 9.6-A	Sediment and Water Quality Characterisation Studies
Appendix 9.6-B	Sediment PCB Concentrations and Sediment Thresholds for Increased Uptake in Southern Resident Killer Whales
Appendix 9.6-C	Dredging Studies – Dispersion Modelling
Appendix 9.6-D	Rationale for Exclusion of Other Certain and Reasonably Foreseeable Projects and Activities in the Surficial Geology and Marine Sediment Assessment of Cumulative Change
Appendix 9.7-A	Rationale for Exclusion of Other Certain and Reasonably Foreseeable Projects and Activities in the Marine Water Quality Assessment of Cumulative Change
Appendix 9.8-A	Construction and Terminal Activity Underwater Noise Modelling Study Technical Report
Appendix 9.8-B	Regional Commercial Vessel Traffic Underwater Noise Modelling Study Technical Report
Appendix 9.8-C	Rationale for Inclusion / Exclusion of Other Certain and Reasonably Foreseeable Projects and Activities in the Underwater Noise Assessment of Cumulative Change

**AUTHORSHIP AND PROFESSIONAL CREDENTIALS****Environmental Impact Statement**

<b>Section</b>	<b>Contributors and Credentials</b>	<b>Affiliation</b>
8.0 Effects Assessment Methods	Pamela O'Hara, R.P.Bio.	Hemmera Envirochem Inc.
	Celesa Horvath, M.Sc.	Ventus Development Services Inc.
	Pat Miller, M.Sc., R.P.Bio.	Hemmera Envirochem Inc.
9.1 Climate, Coastal Conditions, and Geotechnical Considerations	Pat Miller, M.Sc., R.P.Bio.	Hemmera Envirochem Inc.
	Roberto Olivera, PhD, P.Eng.	Golder Associates Ltd.
	Rowland Atkins, M.Sc., P.Geo.	Golder Associates Ltd.
	Upul Atukorala, PhD, P.Eng.	Golder Associates Ltd.
9.2 Air Quality	Dan Hrebnyk, M.Sc.	SENES Consultants Limited
	Jennifer Hodowsky, P.Eng.	SENES Consultants Limited
	Sandy Willis, M.Eng., P.Eng.	SENES Consultants Limited
	Alex Schutte, B.Sc., EP	Levelton Ltd.
9.3 Noise and Vibration	Clair W. Wakefield, M.A.Sc., P.Eng.	Wakefield Acoustics Ltd.
	Andrew Williamson, P.Eng.	Wakefield Acoustics Ltd.
9.4 Light	Esen Cintosun, PhD, P.Eng.	Golder Associates Ltd.
	Danny da Silva, B.Sc., B.A.Sc., P.Eng.	Golder Associates Ltd.
9.5 Coastal Geomorphology	Derek Ray, M.Sc., P.Geo.	Northwest Hydraulic Consultants
	Charlene Menezes, M.Eng., P.Geo.	Northwest Hydraulic Consultants
9.6 Surficial Geology and Marine Sediment	Doug Bright, PhD, R.P.Bio., P.Biol.	Hemmera Envirochem Inc.
	Jennifer Steele, P.Chem., MMM	Hemmera Envirochem Inc.
9.7 Marine Water Quality	Doug Bright, PhD, R.P.Bio., P.Biol.	Hemmera Envirochem Inc.
	Jennifer Steele, P.Chem., MMM	Hemmera Envirochem Inc.
9.8 Underwater Noise	Sonya Meier, M.Sc., R.P.Bio.	Hemmera Envirochem Inc.

**Appendices**

Appendix	Contributors and Credentials	Affiliation
Appendix 9.2-A Air Quality Study	Dan Hrebenyk, M.Sc.	SENES Consultants Limited
	Jennifer Hodowsky, P.Eng.	SENES Consultants Limited
	Sandy Willis, M.Eng., P.Eng.	SENES Consultants Limited
	Svetlana Music	SENES Consultants Limited
	Jennifer Kirkaldy B.A.Sc. (Ch.E.)	SENES Consultants Limited
	Alex Schutte, B.Sc., EP	Levelton Ltd.
Appendix 9.3-A Roberts Bank Terminal 2 Noise and Vibration Study	Clair W. Wakefield, M.A.Sc., P.Eng.	Wakefield Acoustics Ltd.
	Andrew Williamson, P.Eng.	Wakefield Acoustics Ltd.
Appendix 9.4-A Light Assessment Technical Report	Danny da Silva, B.Sc., B.A.Sc., P.Eng.	Golder Associates Ltd.
	Esen Cintosun, PhD, P.Eng.	Golder Associates Ltd.
Appendix 9.5-A Coastal Geomorphology Study	Derek Ray, M.Sc., P.Geo.	Northwest Hydraulic Consultants
	Charlene Menezes, M.Eng., P.Geo.	Northwest Hydraulic Consultants
Appendix 9.6-A Sediment and Water Quality Characterisation Studies	Doug Bright, PhD, R.P.Bio., P.Biol.	Hemmera Envirochem Inc.
	Jennifer Steele, P.Chem., MMM	Hemmera Envirochem Inc.
Appendix 9.6-B Sediment Characteristics in the Context of Construction-related Sediment Re-suspension and Marine Discharge	Doug Bright, PhD, R.P.Bio., P.Biol.	Hemmera Envirochem Inc.
	Jennifer Steele, P.Chem., MMM	Hemmera Envirochem Inc.
	Julien Traverse, P.Eng., M.B.A.	Hemmera Envirochem Inc.
Appendix 9.6-C Dredging Studies - Dispersion Modelling	Jim Stronach, Ph.D., P.Eng.	Tetra Tech EBA
	Daniel Potts, P.Eng., M.A.Sc.	Tetra Tech EBA

Appendix	Contributors and Credentials	Affiliation
Appendix 9.8-A Construction and Terminal Activity Underwater Noise Modelling Study Technical Report	Jennifer Wladichuk, B.Sc., PhD	JASCO Applied Sciences (Canada) Ltd.
	Graham Warner, B.Sc., DipEd, M.Sc. (In Progress)	JASCO Applied Sciences (Canada) Ltd.
	Andrew McCrodan, B.Sc.	JASCO Applied Sciences (Canada) Ltd.
	Alexander MacGillivray, B.Sc., M.Sc., Grad. Cert. P.M.	JASCO Applied Sciences (Canada) Ltd.
	David Hannay, B.Sc., M.Sc.	JASCO Applied Sciences (Canada) Ltd.
Appendix 9.8-B Regional Commercial Vessel Traffic Underwater Noise Modelling Study Technical Report	Alexander MacGillivray, B.Sc., M.Sc., Grad. Cert. P.M.	JASCO Applied Sciences (Canada) Ltd.
	Zizheng Li, M.Sc.	JASCO Applied Sciences (Canada) Ltd.
	Graham Warner, B.Sc., DipEd, M.Sc. (In Progress)	JASCO Applied Sciences (Canada) Ltd.
	Caitlin O’Neill, B.Sc., M.Sc. (In Progress)	JASCO Applied Sciences (Canada) Ltd.
	Jeremy Gosselin, B.Sc.	JASCO Applied Sciences (Canada) Ltd.
	David Hannay, B.Sc., M.Sc.	JASCO Applied Sciences (Canada) Ltd.