EROSION AND SEDIMENT CONTROL GENERAL NOTES:

- CONTRACTOR SHALL CONSIDER ALL THE REQUIREMENTS IN THE ENVIRONMENTAL PROTECTION PLAN (EPP), WILDLIFE MANAGEMENT PLAN AND FOLLOW PROGRAM AS WELL AS THE ENVIRONMENTAL PROTECTION SECTION 01560 DURING THE IMPLEMENTATION OF THE EROSION AND CONTROL (ESC) MEASURES SHOWN IN THE PLANS.
- DETAILED SITE SPECIFIC METHODS AND DRAWINGS FOR ESC MEASURES SHALL BE DESIGNED BY THE CONTRACTOR IN ACCORDANCE WITH THE GENERAL REQUIREMENTS SHOWN ON THE EROSION AND SEDIMENT CONTRACT DRAWINGS AND THE CONTRACTOR METHOD OF CONSTRUCTION.
- ESC PRACTICES SHALL BE CONSISTENT WITH THE CONSOLIDATED CONDITIONS AND COMMITMENTS AS DETAILED IN APPENDIX A OF SECTION
- THE CONTRACTOR SHALL INSTALL, INSPECT AND MAINTAIN ESC MEASURES IN ACCORDANCE WITH THE APPROVED EROSION AND SEDIMENT CONTROL
- THE CONTRACTOR SHALL ENSURE THAT ESC MEASURES ARE IN PLACE PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION ACTIVITIES INCLUDING VEGETATION CLEARING AND GRUBBING AND REMAIN IN PLACE UNTIL ALL DISTURBED AREAS ARE FULLY STABILIZED SO AS TO RETAIN SEDIMENT ONSITE AND PREVENT ENTRY INTO ANY WATERCOURSES.
- THE ESC STRATEGIES OUTLINED ON THE APPROVED PLANS ARE NOT STATIC AND MAY NEED TO BE UPGRADED/AMENDED AS SITE/WEATHER CONDITIONS CHANGE TO MINIMIZE SEDIMENT LADEN RUNOFF FROM LEAVING THE WORK AREAS.
- IF THE PRESCRIBED MEASURES ARE NOT EFFECTIVE IN MITIGATING THE ACCIDENTAL RELEASE OF SEDIMENT OR DELETERIOUS SUBSTANCE, ALTERNATIVE MEASURES MUST BE IMPLEMENTED IMMEDIATELY TO CIRCUMVENT AND AVOID POTENTIAL ECOLOGICAL IMPACTS AS A PRIORITY AND MINIMIZE POTENTIAL ECOLOGICAL IMPACTS IF THEY COULD NOT BE AVOIDED.
- FOR LOW RISK ACTIVITIES. THE CONTRACTOR SHALL PROVIDE AN ENVIRONMENTAL SITE INSPECTOR PER ENVIRONMENTAL PROTECTION SECTION 01560 TO INSPECT ESC MEASURES ON A WEEKLY BASIS AS WELL AS PRIOR TO AND FOLLOWING HEAVY PRECIPITATION EVENTS (I.E. 10mm IN 24HRS) AND SIGNIFICANT SNOW MELTS TO ENSURE THE MEASURES ARE FUNCTIONING PROPERLY, MAINTAINED AND UPGRADED AS REQUIRED. IF ESC MEASURES ARE NOT FUNCTIONING PROPERLY. THE CONTRACTOR SHALL MAKE REPAIRS IMMEDIATELY. LOW RISK WORKS INCLUDE CONSTRUCTION ACTIVITIES OCCURRING AWAY FROM SENSITIVE NATURAL AREAS AS IDENTIFIED. HIGH RISK ACTIVITIES SHALL BE MONITORED DAILY. HIGH RISK ACTIVITIES OCCUR IN CLOSE PROXIMITY TO SENSITIVE NATURAL AREAS AND INCLUDE IN-OR NEAR-WATER WORKS, CONCRETE WORKS, DEWATERING, VEGETATION CLEARING AND GRUBBING, AND THOSE WHERE SHOULD ESC FAIL, THERE IS LIKELY IMPACT TO SENSITIVE NATURAL AREAS. SENSITIVE NATURAL AREAS ARE IDENTIFIED IN THE DRAWING PACKAGE.
- THE CONTRACTOR SHALL PROVIDE ADDITIONAL SEDIMENT AND EROSION CONTROL MEASURES TO BE KEPT ON SITE FOR EMERGENCIES AND REPAIRS.
- ALL DAMAGED ESC MEASURES SHALL BE REPAIRED/REPLACED WITHIN ONE (1)
- 11. ALL WORKS SHALL BE CONDUCTED SUCH THAT WORKS IN SEVERE WEATHER ARE AVOIDED AS PER THE EPP. THE CONTRACTOR SHALL MONITOR WEATHER FORECASTS IN ADVANCE AND PLAN WORKS ACCORDINGLY. REFER TO THE ACCIDENT AND MALFUNCTIONS PLAN.
- 12. ALL IN-WATER WORK SHALL ENDEAVOR TO OCCUR DURING LOW FLOW CONDITIONS. IN-WATER WORK AREAS SHALL BE ISOLATED SUCH THAT WORKS ARE CONDUCTED IN THE DRY.
- THE CONTRACTOR SHALL MINIMIZE DISTURBANCES TO THE WATERCOURSE BANKS DURING CONSTRUCTION, BY RESTRICTING ACCESS AND MINIMIZING THE AREA REQUIRED FOR CONSTRUCTION

O NOT SCALE THIS DOCUMENT. ALL MEASUREMENTS JST BE OBTAINED FROM STATED DIMENSIONS

AECOM CANADA LTD.

- 14. THE LIMITS OF CONSTRUCTION, WHICH INCLUDES SENSITIVE NATURAL AREAS AS DEFINED IN THE DRAWING PACKAGE WILL BE MARKED IN THE FIELD TO PROTECT RETAINED NATURAL AREAS.
- ALL ACCESS TO WORK SITES SHALL BE FROM EITHER SIDE OF ANY WATERCOURSE EXCEPT FOR THE CASE OF THE TWO PRE-DETERMINED TEMPORARY CROSSINGS OF INDIAN CREEK, ONCE CONSTRUCTED. THE TWO PRE-DETERMINED TEMPORARY CROSSINGS OF INDIAN CREEK AS PER THE CONTRACT DRAWINGS CAN BE USED.
- THE CONTRACTOR SHALL ENSURE THAT DEWATERING DURING CONSTRUCTION WORK SHALL PASS THROUGH A FILTER BAG OR ROCK FLOW CHECK DAM WITH FILTER CLOTH PRIOR TO RELEASE INTO ANY WATERCOURSE. THE FILTER BAG(S) SHOULD BE LOCATED A MINIMUM OF 30M FROM THE RECEIVING WATERCOURSE BANK. ALL WATER AND PUMP INTAKE STRUCTURES LOCATED IN FISH-BEARING WATER SHALL BE INSTALLED AND OPERATED IN A MANNER THAT MITIGATES THE INCIDENTAL CAPTURE OF FISH BY ENTRAINMENT AND IMPINGEMENT AND IS CONSISTENT WITH THE FISHERIES ACT AND PER THE ENVIRONMENTAL PROTECTION SECTION 01560. SHOULD THE FILTER BAG NEED TO BE WITHIN 30m OF THE RECEIVING WATERCOURSE OR IS LOCATED WITHIN SPARSELY VEGETATED/DISTURBED AREA, ADDITIONAL CONTAINMENT AND MITIGATION SUCH AS A STRAW BALE ENCLOSURE, DETENTION POND, SUMP OR SIMILAR STRUCTURE IS REQUIRED.
- ALL GROUND DISTURBANCE ACTIVITIES NEAR WATERCOURSES, INCLUDING EXCAVATION AND STRIPPING WORKS, SHALL BE AVOIDED DURING PERIODS OF WET WEATHER.
- BEFORE HOLIDAYS, WEEKENDS, AND EXTENDED NON-WORK PERIODS, EXPOSED SOILS MUST BE STABILIZED TO ENSURE STABILITY DURING RAIN
- ALL GRADES WITHIN THE REGULATORY FLOODPLAIN AS DEFINED IN THE CONTRACT DRAWINGS SHALL BE MAINTAINED AND RESTORED EXCEPT WHERE GRADING AND FLOOD PLAIN ALTERATIONS ARE PROPOSED
- ALL CONSTRUCTION MATERIALS. EQUIPMENT AND ESC MEASURES SHALL ARRIVE ON SITE IN A CLEAN CONDITION FREE OF DEBRIS AND SHALL BE STORED AND OPERATED IN A WAY THAT PREVENTS DELETERIOUS SUBSTANCES FROM ENTERING ANY WATERCOURSE. CONSTRUCTION AND EXCAVATED MATERIALS SHALL BE LOCATED AND MAINTAINED AWAY (30M MINIMUM) FROM WATERCOURSES AND OTHER DRAINAGE FEATURES. STORM INLETS, CATCHBASINS AND MAINTENANCE HOLES.
- BIODEGRADABLE OIL SHALL BE USED IN ALL EQUIPMENT OPERATING IN OR NEAR WATER FOR CREEK ALIGNMENT ACTIVITIES. ALL VEHICLE AND EQUIPMENT REFUELING AND MAINTENANCE SHALL BE CONDUCTED A MINIMUM OF 30M AWAY FROM ANY WETLAND OR WATERBODY, STORM INLETS, CATCH BASINS AND MAINTENANCE HOLES. IN ADDITION, A SPILL KIT CONTAINING SUITABLE ABSORBENT MATERIAL MUST BE STORED ON SITE PER **ENVIRONMENTAL PROTECTION SECTION 01560.**
- 22. ESC MEASURES SHALL BE APPLIED TO ALL STAGING AND STORAGE AREAS.
- 23. STAGING AREAS MUST BE LOCATED A MINIMUM OF 30 m AWAY FROM ANY WATERCOURSE.
- 24. STOCKPILE AREAS SHALL BE MANAGED AND MAINTAINED AS PER THE SOILS MANAGEMENT PLAN AND NOT BE WITHIN 30m OF ANY WATERCOURSE.
- 25. HAZARDOUS MATERIALS MUST BE STOCKED ABOVE THE REGULATORY FLOOD
- THE CONTRACTOR SHALL COLLECT AND TREAT ALL WASTEWATERS AND WASH WATERS, TAKING INTO ACCOUNT THE CANADIAN COUNCIL OF MINISTERS OF THE ENVIRONMENT'S CANADIAN WATER QUALITY GUIDELINES FOR THE PROTECTION OF AQUATIC LIFE, BEFORE DISCHARGING THEM IN ANY WETLAND OR WATERBODY.
- THE CONTRACTOR SHALL IMPLEMENT MEASURES TO PREVENT WET CONCRETE OR CEMENT-LADEN WATER, INCLUDING HIGH pH RUN-OFF OCCURRING DURING CONCRETE WORK, FROM ENTERING ANY WETLAND OR WATERBODY DURING CONSTRUCTION. THE CONTRACTOR SHALL ESTABLISH WASHOUT AREAS BEFORE BEGINNING CONCRETE WORK.

- PRIVATE ROADS USING GRAVELED OR PAVED EXITS AND PARKING AREAS. MUD MATS ARE TO BE PLACED AT ALL EXIT POINTS OF EACH ACCESS TO THE
- 29. ESC MEASURES SHALL NOT BE REMOVED UNTIL PERMANENT VEGETATION IS ESTABLISHED OR THE SITE IS OTHERWISE FULLY STABILIZED. TEMPORARY FLOW DIVERSION SHOULD BE PROVIDED FOR ALL CULVERT
- EXTENSIONS, REPLACEMENTS, ADDITIONS AND TEMPORARY CROSSINGS. THE MEANS OF CONVEYING TEMPORARY FLOWS DURING CONSTRUCTION (DAM AND PUMP, FLUME, ETC) SHOULD CONSIDER THE DURATION OF THE WORKS, THE TIMING OF THE WORKS (SPRING VS. SUMMER), THE SIZE OF THE UPSTREAM DRAINAGE AREA, THE POTENTIAL DAMAGES TO EQUIPMENT AND THE IMPACT OF THE STORM EVENT.
- THE CONTRACTOR SHALL PROTECT ALL EXPOSED SURFACES, AND CONTROL ALL RUN-OFF DURING CONSTRUCTION.
- THE CONTRACTOR SHALL PROTECT ALL CATCHBASINS, MANHOLES, AND PIPE ENDS FROM SEDIMENT INTRUSION.
- THE CONTRACTOR SHALL DISPOSE OF ALL COLLECTED SEDIMENT TO AN APPROVED SITE PER THE SOILS MANAGEMENT PLAN AND APPROVAL OF CN'S ENVIRONMENTAL MONITOR AND QP.
- THE CONTRACTOR SHALL KEEP ALL SUMPS CLEAN DURING CONSTRUCTION. THE CONTRACTOR SHALL PREVENT WIND-BLOWN DUST THROUGH IMPLEMENTATION OF APPROPRIATE DUST MITIGATION MEASURES ON ALL
- **EXPOSED SURFACES** THE CONTRACTOR SHALL ENSURE ALL DEWATERING EFFLUENT IS DISPOSED
- OF IN ACCORDANCE WITH ALL APPLICABLE REGULATIONS FLOW CHECK DAM LOCATIONS SHOWN ON ESC DRAWINGS ARE APPROXIMATE ONLY. PRECISE LOCATIONS AND EXTENT OF PROTECTION REQUIRED ARE TO BE DETERMINED IN THE FIELD BY CN'S ENVIRONMENTAL MONITOR. TEMPORARY ROCK CHECK DAMS TO BE INSTALLED IN EXISTING AND PROPOSED DITCHES EVERY 50m.
- ROCK CHECK DAMS TO BE INSTALLED AS PER OPSD 219.210 AND OPSD 219.211. HEAVY DUTY SILT FENCING TO BE INSTALLED AS PER OPSD 219.130. 39.
- 40. EROSION MATTING TO BE INSTALLED AS PER MANUFACTURER SPECIFICATIONS.
- SILT FENCING TO BE INSTALLED AT TOE OF SLOPE FOR ALL DISTURBED SURFACES.
- 42. SILT CURTAIN OR STRAW BALE FILTER TO BE INSTALLED AT ALL MAJOR DITCH OUTLET POINTS.
- 43. ANY RE-GRADED CHANNEL AREAS WILL BE RE-STABILIZED WITH NATURAL SUBSTRATE (COBBLE) BEFORE FLOW IS REINSTATED.
- THE CONTRACTOR SHALL NOTIFY CN'S ENVIRONMENTAL MONITOR 72 HOURS BEFORE ANY IN-WATER WORK, INCLUDING BUT NOT LIMITED TO CONSTRUCTION OF ANY WATERCOURSE OR WATER BODY CROSSING OR DIVERSIONS, TO ENSURE ANY NECESSARY FISH SALVAGE OPERATIONS ARE CONDUCTED PER SECTION 01560.
- PROGRESSIVE RECLAMATION TO BE UNDERTAKEN IN AREAS WHERE CONSTRUCTION/GRADING IS COMPLETE PER THE RESTORATION AND ENHANCEMENT PLAN

CULVERTS

COFFERDAM NOTES:

- 1. CONTRACTOR SHALL DESIGN AND INSTALL COFFERDAM IN ACCORDANCE WITH THE DOCUMENT EROSION AND SEDIMENT CONTROL GUIDELINE FOR URBAN CONSTRUCTION (2019)
- CONTRACTOR SHALL SUBMIT THE DESIGN OF COFFERDAM FOR APPROVAL TO THE ENGINEER PRIOR TO CONSTRUCTION.
- 3. WORK IS TO BE COMPLETED ON DRY WEATHER DAYS ONLY. CONTRACTOR IS TO MONITOR WEATHER FORECAST 5 DAYS PRIOR TO COMMENCEMENT OF WORK.
- 4. CONTRACTOR SHALL MONITOR WEATHER FORECAST AND WHERE WET WEATHER EVENTS MAY EXCEED THE COFFERDAM, REMOVE ALL EQUIPMENT AND CEASE IN-WATER WORK. AFTER FLOODING SUBSIDES, DEWATER FROM WITHIN THE ISOLATED ZONE TO APPROVED SEDIMENTATION CONTROL FEATURES, MAKE ANY REPAIRS NECESSARY TO THE COFFERDAM AND CONTINUE IN-WATER WORKS.
- 5. PEA-GRAVEL BAGS OR A SUITABLE ALTERNATIVE IS TO BE USED FOR THE COFFERDAM. DESIGN AND MATERIAL TO BE APPROVED BY CN'S ENVIRONMENTAL MONITOR PRIOR TO START OF CONSTRUCTION.


SILT FENCE NOTES:

SILT FENCE SHALL BE PLACED AT LOCATIONS SHOWN ON THE CONTRACT DRAWINGS INCLUDING THE CONSTRUCTION LIMITS, LAYDOWN AREAS, ACCESS ROUTES AND SEDIMENT STORAGE AREAS.

ALL SILT FENCES SHALL BE ANCHORED AT OPENINGS AND START/END LOCATIONS WITH J-HOOKS.


RIP-RAP AND ROCK PROTECTION NOTES:

- . RIP-RAP TO OPSD 810.010 TO THE THICKNESS AND SIZES SPECIFIED IN THE CONTRACT DRAWINGS ARE TO BE INSTALLED AT THE NEW CULVERTS INLET AND OUTLET POINTS AS WELL AS OVER EVERY OTHER POINT OF POTENTIAL EROSION POINTS DUE TO WATER DISCHARGE OR CHANGE OF DIRECTION AS SHOWN IN THE CONTRACT DRAWINGS.
- 2. ALL ROCK PROTECTION REQUIRED ALONG FISH-BEARING WATERCOURSES AND TRIBUTARIES SHALL CONSIST OF RIVERSTONE OF THE TYPE SPECIFIED IN THE CONTRACT DRAWINGS



COFFERDAM - SCHEMATIC PLAN

AECOM



MUD MAT - SCHEMATIC PLAN

MILTON LOGISTICS HUB - HALTON SUBDIVISION - PHASE 1

DRAWING NUMBER

01-G-1000

ISSUE/REVISION

Α


EROSION AND SEDIMENT CONTROL PLANS

GENERAL NOTES, DETAILS AND KEY PLAN

GENERAL DRAWINGS

PROJECT NUMBER

60579933




JL JOM LP LB


DRN CHK DES ENG IDR AF


A 21/04/30 ISSUED FOR TENDER


R YY/MM/DD


ISSUE/REVISION DESCRIPTION



















NOTES:

- 1.EROSION AND SEDIMENT CONTROL MEASURES SHOWN IN DRAWINGS 01-G-1011 TO 01-G-1016 ARE PROPOSED FOR THE INSTALLATION OF THE CULVERTS ONLY. GRADING WORKS FOR THE NEW TRACKS WILL BE CONSTRUCTED ONCE THESE ARE IN PLACE.
- 2.WHERE EXISTING CULVERT REMOVALS ARE REQUIRED, ADDITIONAL FIELD FIT ESC MEASURES SHALL BE INSTALLED BY THE CONTRACTOR TO FULLY CONTAIN THE WORK AREA AND MINIMIZE THE RISK OF SEDIMENT MOBILIZATION TOWARDS NEWLY INSTALLED CULVERT.
- 3.ESC MEASURES ASSOCIATED WITH ACCESS ROUTES TO BE FIELD FIT BY CONTRACTOR .NO-GO AREAS AND VEGETATION BUFFER ZONES SHALL BE CONSIDERED WHEN DETERMINING ACCESS
- 4.NEW RIP-RAP SHOWN AT NEW CULVERTS INLET AND OUTLET POINTS IS REQUIRED AS SOON AS FLOW IS CONVEYED THROUGH THE CULVERTS, BUT IS TO BE ADJUSTED WHERE REQUIRED TO FINAL GRADING SLOPES AS SHOWN ON TRACK AND GRADING DRAWINGS.

LEGEND





DEWATERING SUMP-PUMP IN CLEARSTONE OR AS SPECIFIED IN THE CONTRACTOR'S BY-PASS SYSTEM (UPSTREAM)



DOWNSTREAM OF BY-PASS SYSTEM. DISCHARGE OVER RIP-RAP WITH OVERFLOW OR AS DESIGNED BY THE CONTRACTOR

A 21/04/30 ISSUED FOR TENDER JL JOM LP LB

ISSUE/REVISION DESCRIPTION

DRN CHK DES ENG IDR APP

I/R YY/MM/DD



,	REGION	SUBDIVISION	MILE
	-	HALTON	38.72 - 40.9
	CN PROJECT NO.	CN DRAWING NO.	
	-	-	

CN

MILTON LOGISTICS HUB - HALTON SUBDIVISION - PHASE 1
GENERAL DRAWINGS
EROSION AND SEDIMENT CONTROL PLANS
CULVERTS INSTALLED DURING PHASE 1 - STA. 65+325

PROJECT NUMBER

DRAWING NUMBER


01-G-1014

© 2021 AECOM CANADA LTD. ALL RIGHTS RESERVED. THIS DOCUMENT IS PROTECTED BY COPYRIGHT LAW AND MAY NOT BE REPRODUCED IN ANY MANNER, OR FOR ANY PURPOSE EXCEPT BY THE WRITTEN PERMISSION OF AECOM CANADA LTD.

OO NOT SCALE THIS DOCUMENT. ALL MEASUREMENTS MUST BE OBTAINED FROM STATED DIMENSIONS.

60579933

ISSUE/REVISION



CULVERT 3 SOUTH PORTION & TEMPORARY CULVERTS AT Mi. 40.62

JL JOM LP LB

DRN CHK DES ENG IDR APP




ISSUE/REVISION DESCRIPTION

I/R YY/MM/DD

NOTES:

- 1.EROSION AND SEDIMENT CONTROL MEASURES SHOWN IN DRAWINGS 01-G-1011 TO 01-G-1016 ARE PROPOSED FOR THE INSTALLATION OF THE CULVERTS ONLY. GRADING WORKS FOR THE NEW TRACKS WILL BE CONSTRUCTED ONCE THESE ARE IN PLACE.
- 2.WHERE EXISTING CULVERT REMOVALS ARE REQUIRED , ADDITIONAL FIELD FIT ESC MEASURES SHALL BE INSTALLED BY THE CONTRACTOR TO FULLY CONTAIN THE WORK AREA AND MINIMIZE THE RISK OF SEDIMENT MOBILIZATION TOWARDS NEWLY INSTALLED CULVERT.
- 3.ESC MEASURES ASSOCIATED WITH ACCESS ROUTES TO BE FIELD FIT BY CONTRACTOR .NO-GO AREAS AND VEGETATION BUFFER ZONES SHALL BE CONSIDERED WHEN DETERMINING ACCESS
- 4.NEW RIP-RAP SHOWN AT NEW CULVERTS INLET AND OUTLET POINTS IS REQUIRED AS SOON AS FLOW IS CONVEYED THROUGH THE CULVERTS, BUT IS TO BE ADJUSTED WHERE REQUIRED TO FINAL GRADING SLOPES AS SHOWN ON TRACK AND GRADING DRAWINGS.

LEGEND



SUBDIVISION

DOWNSTREAM OF BY-PASS SYSTEM.
DISCHARGE OVER RIP-RAP WITH OVERFLOW

OR AS DESIGNED BY THE CONTRACTOR

HALTON 38.72 - 40.98 ON PROJECT NO. CN DRAWING NO.

MILTON LOGISTICS HUB - HALTON SUBDIVISION - PHASE 1 GENERAL DRAWINGS EROSION AND SEDIMENT CONTROL PLANS CULVERTS INSTALLED DURING PHASE 1 - CULVERT 3 - STA. 65+400

PROJECT NUMBER

60579933

DRAWING NUMBER 01-G-1015

ISSUE/REVISION Α

PROFESSIONAL SEALS DO NOT SCALE THIS DOCUMENT. ALL MEASUREMENTS MUST BE OBTAINED FROM STATED DIMENSIONS. © 2021 AECOM CANADA LTD. ALL RIGHTS RESERVED. A 21/04/15 ISSUED FOR TENDER AND MAY NOT BE REPRODUCED IN ANY MANNER, OR FOR

ANY PURPOSE EXCEPT BY THE WRITTEN PERMISSION OF

AECOM CANADA LTD.

AECOM

